


ESTIMATED QUANTITIES

| BID NO. | SPEC. NO. | ITEM | UNIT | TOTAL ESTIMATED QTY. |
|---------|-----------|-------------------------------------|----------|----------------------|
| 1 | 2.9.1 | 8" PVC SANITARY SEWER | L.F. | 1680 |
| 2 | 2.9.5 | 6" HDPE FORCEMAIN | L.F. | 3168 |
| 3 | 2.9.12 | MANHOLES | V.L.F. | 146 |
| 4 | 4.11.1 | AIR RELEASE VAULT | EACH | 3 |
| 5 | 4.13.0 | BORING OR JACKING FOR SEWERS | L.F. | 946 |
| 6 | 2.9.16 | TYPE "D" LAWN REPLACEMENT | S.Y. | 7500 |
| 7 | 2.7.2 | SIDEWALK REPLACEMENT | S.F. | 750 |
| 8 | 2.8.1 | SILT FENCE, DELIVERED & INSTALLED | L.F. | 3000 |
| 9 | 2.8.1 | EROSION CONTROL FOR DEWATERING | LUMP SUM | 1 |
| 10 | 2.7.3 | TYPE "A" PAVEMENT REPLACEMENT | S.F. | 200 |
| 11 | 2.7.3 | TYPE "C" PAVEMENT REPLACEMENT | S.F. | 500 |
| 12 | -- | MOBILIZATION | LUMP SUM | 1 |
| 13 | -- | SALVAGE P.R. TIES, HARDWARE & RAILS | L.F. | 2860 |
| 14 | -- | SEWERAGE LIFT STATION | LUMP SUM | 1 |

STANDARD DETAIL DRAWINGS

| THE FOLLOWING WisDOT STANDARD DETAIL DRAWINGS SHALL APPLY ON THIS PROJECT. | |
|--|--|
| PLATE NO. | DESCRIPTION |
| 8 E 8-2 | TYPICAL INSTALLATIONS OF EROSION BALES |
| 8 E 9-4 | SILT FENCE |
| 15C12-2 | TRAFFIC CONTROL FOR LANE CLOSURE (SUITABLE FOR MOVING OPERATION) |



PIPE BEDDING DETAIL FOR PVC SEWER PIPE

DRAINAGE STRUCTURES

| STRUCT. NO. | STATION | TYPE & COVER | TOP OF CASTING ELEV. (MH) | INVERT ELEV. | MANHOLE DEPTH - V.L.F. | PIPE SIZE / TYPE | | DRAINS TO | | | REMARKS |
|-------------|---------|--------------|---------------------------|--------------|------------------------|------------------|---------|-------------|-------|-------|-----------------------|
| | | | | | | 8" PVC | 6" HDPE | NO. | GRADE | ELEV. | |
| 1 | 1+00 | | 98.50 | 92.50 | 6.00 | 355 | | 2 | 0.004 | 91.08 | FUTURE WORK BY OTHERS |
| 2 | 4+55 | | 99.01 | 90.98 | 8.03 | 355 | | 3 | 0.004 | 89.56 | FUTURE WORK BY OTHERS |
| 3 | 8+10 | | 99.43 | 89.46 | 9.97 | 355 | | 4 | 0.004 | 88.04 | FUTURE WORK BY OTHERS |
| 4 | 11+65 | | 99.18 | 87.94 | 11.24 | 355 | | 5 | 0.004 | 86.52 | FUTURE WORK BY OTHERS |
| 5 | 15+20 | | 98.84 | 86.42 | 12.42 | 355 | | 6 | 0.004 | 85.00 | FUTURE WORK BY OTHERS |
| 6 | 18+75 | | 98.80 | 84.90 | 13.90 | 355 | | 7 | 0.004 | 83.48 | FUTURE WORK BY OTHERS |
| 7 | 22+30 | | 99.04 | 83.38 | 15.66 | 400 | | 8 | 0.004 | 81.78 | |
| 8 | 26+30 | | 98.31 | 81.68 | 16.63 | 60 | | 9 | 0.004 | 81.44 | |
| 9 | 26+90 | | 97.59 | 81.34 | 16.25 | 400 | | 10 | 0.004 | 79.74 | |
| 10 | 30+90 | | 96.08 | 79.64 | 16.44 | 400 | | 11 | 0.004 | 78.04 | |
| 11 | 34+90 | | 96.67 | 77.94 | 18.73 | 400 | | 12 | 0.004 | 76.34 | |
| 12 | 38+90 | | 97.50 | 66.0 | LIFT STATION | | 3168 | EXIST. M.H. | -- | 98.9 | FORCEMAIN |

CERTIFIED BY *[Signature]*
PROFESSIONAL ENGINEER

REG. NO. E-27533 DATE 2/17/97

ESTIMATED QUANTITIES / DETAILS

Proj. No. 97188.3

Sheet No. 2.0 of 8 Sheets