

LEVELS ON = 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63

CLEARING AND GRUBBING			
STATION TO STATION	LOCATION	(20102)	(20105)
		CLEARING I.D.	GRUBBING I.D.
GRAND AVE.			
101+10.34 - 122+11.00	LT & RT	144	144
ITEM TOTAL		144	144

REMOVING CURB, CURB & GUTTER			
STATION TO STATION	LOCATION	(20403)	(20405)
		REMOVE CURB L.F.	REMOVE CURB & GUTTER L.F.
GRAND AVE.			
101+10.34 - 105+30.18	LT	435	40
101+10.34 - 105+30.18	RT	406	9
105+30.18 - 109+50.23	LT	467	43
105+30.18 - 109+50.23	RT	420	0
109+50.23 - 113+70.18	LT	459	0
109+50.23 - 113+70.18	RT	441	0
113+70.18 - 117+90.66	LT	448	0
113+70.18 - 117+90.66	RT	449	0
117+90.66 - 122+11.00	LT	463	0
117+90.66 - 122+11.00	RT	453	0
ITEM TOTAL		4441	92

REMOVING CONCRETE SIDEWALK		
STATION TO STATION	LOCATION	(20406)
		REMOVING CONCRETE SIDEWALK S.Y.
GRAND AVE.		
101+10.34 - 105+30.18	LT	262
101+10.34 - 105+30.18	RT	250
105+30.18 - 109+50.23	LT	272
105+30.18 - 109+50.23	RT	257
109+50.23 - 113+70.18	LT	274
109+50.23 - 113+70.18	RT	252
113+70.18 - 117+90.66	LT	275
113+70.18 - 117+90.66	RT	277
117+90.66 - 122+11.00	LT	274
117+90.66 - 122+11.00	RT	277
ITEM TOTAL		2670

REMOVING STORM SEWER					
STATION TO STATION	LOCATION	(20414)	(20415)	(20496)	(90030E)
		REMOVE MH EACH	REMOVE CB EACH	SEALING PIPES EACH	REMOVE SEWER PIPE L.F.
GRAND AVE.					
105+10.88	LT		1		
105+49.13	LT		1		
105+09.98 - 105+10.88	LT			1	38
105+10.88 - 105+49.13	LT				39
109+28.59	LT	1			
109+28.59	LT			1	48
109+72.88	LT	1			
109+28.29 - 109+72.88	LT				45
117+71.52	LT		1		
117+71.52 - 117+73.94	LT			1	18
117+71.52 - 118+04.57	LT				34
118+04.57	LT	1			
120+15.18 - 120+45.57	RT				30
120+45.57	RT	1			
120+45.57 - 120+46.17	LT - RT				65
120+46.17	LT	1			
ITEM TOTAL		5	3	3	316

EARTHWORK SUMMARY				
STATION TO STATION	LOCATION	(20501)	FILL *	WASTE
		COMMON EXCAVATION C.Y.	C.Y.	C.Y.
GRAND AVE.				
101+50 - 122+00	MAINLINE	7648	115	7533
GRADING				
101+50 - 122+00	MAINLINE	571	0	571
EBS				
BROADWAY ST., 11TH ST., 12TH ST., 13TH ST., 14TH ST., BELKNAP ST.	SIDE ROADS	700	10	690
GRADING				
ITEM TOTAL		8919	125	8794

\* EXPANSION FACTOR 1.3

CRUSHED AGGREGATE BASE COURSE				
STATION TO STATION	LOCATION	CRUSHED AGGREGATE BASE COURSE		
		(30404) BASE COURSE TON	(30420) OPEN GRADED No. 2 TON	(65050) CONSTRUCTION STAKING L.F.
GRAND AVE.				
101+10.34 - 105+30.18	MATCHLINE	793	580	840
105+30.18 - 109+50.23	MATCHLINE	793	580	840
109+50.23 - 113+70.18	MATCHLINE	793	580	840
113+70.18 - 117+90.66	MATCHLINE	795	582	840
117+90.66 - 122+11.00	MATCHLINE	822	636	840
14TH STREET				
34+10.00 - 34+78.00	LT	127		136
13TH STREET				
44+00.00 - 44+78.00	LT	121		156
45+22.00 - 45+70.00	RT	77		96
12TH STREET				
54+36.32 - 54+56.32	LT	48		40
55+00.00 - 55+60.00	RT	113		120
11TH STREET				
64+30.00 - 64+78.00	LT	78		96
65+22.00 - 65+70.00	RT	77		96
ITEM TOTAL		4637	2958	4940

BREAKER RUN STONE		
STATION TO STATION	LOCATION	(30426)
		BREAKER RUN STONE TON
GRAND AVE.		
101+10.34 - 122+11.00	UNDISTRIBUTED	1000
ITEM TOTAL		1000