

LEVELS ON = 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 58, 59, 60, 61, 62, 63

ASPHALTIC PAVING				
STATION TO STATION	LOCATION	(40204)	(40501)	(40722)
		ASPHALTIC MATERIAL FOR TACK COAT	ASPHALTIC MATERIAL FOR PLANT MIXES	ASPHALTIC CONCRETE PAVEMENT TYPE E-1
		GAL	TON	TON
GRAND AVE.				
101+10.34 - 105+30.18	MATCHLINE	65	34	571
105+30.18 - 109+50.23	MATCHLINE	51	27	452
109+50.23 - 113+70.18	MATCHLINE	51	27	452
113+70.18 - 117+90.66	MATCHLINE	51	27	452
117+90.66 - 122+11.00	MATCHLINE	52	28	459
14TH STREET				
34+10.00 - 34+78.00	LT	5	3	46
13TH STREET				
44+00.00 - 44+78.00	LT	5	3	41
45+22.00 - 45+70.00	RT	3	2	28
12TH STREET				
54+36.32 - 54+56.32	LT	2	1	18
55+00.00 - 55+60.00	RT	5	2	41
11TH STREET				
64+30.00 - 64+78.00	LT	3	2	27
65+22.00 - 65+70.00	RT	3	2	28
ITEM TOTAL		297	157	2615

CONCRETE DRIVEWAY		
STATION TO STATION	LOCATION	(41605)
		CONCRETE DRIVEWAY 6-INCH S.Y.
GRAND AVE.		
101+47.78	LT	35.3
104+08.35	LT	61.7
105+30.18	RT	87.2
108+65.13	RT	30.6
116+86.17	LT	33.3
120+34.70	RT	44.9
120+36.52	LT	49.7
120.60.56	RT	43.3
ITEM TOTAL		386

CONCRETE SIDEWALK		
STATION TO STATION	LOCATION	(60204)
		CONCRETE SIDEWALK 4-INCH S.F.
GRAND AVE.		
101+10.34 - 105+30.18	LT	2198
101+10.34 - 105+30.18	RT	2405
105+30.18 - 109+50.23	LT	2871
105+30.18 - 109+50.23	RT	2410
109+50.23 - 113+70.18	LT	2859
109+50.23 - 113+70.18	RT	2815
113+70.18 - 117+90.66	LT	2764
113+70.18 - 117+90.66	RT	3022
117+90.66 - 122+11.00	LT	2753
117+90.66 - 122+11.00	RT	2634
ITEM TOTAL		26731

CONCRETE CURB AND GUTTER			
STATION TO STATION	LOCATION	(60133)	(65055)
		CONCRETE CURB AND GUTTER, 30-INCH, TYPE D L.F.	CONSTRUCTION STAKING, CONCRETE CURB AND GUTTER L.F.
GRAND AVE.			
101+10.34 - 105+30.18	LT	412.6	412.6
101+10.34 - 105+30.18	RT	419.9	419.9
105+30.18 - 109+50.23	LT	408.6	408.6
105+30.18 - 109+50.23	RT	415.9	415.9
109+50.23 - 113+70.18	LT	406.5	406.5
109+50.23 - 113+70.18	RT	408.5	408.5
113+70.18 - 117+90.66	LT	407.0	407.0
113+70.18 - 117+90.66	RT	409.0	409.0
117+90.66 - 122+11.00	LT	426.9	426.9
117+90.66 - 122+11.00	RT	426.9	426.9
14TH STREET			
34+10.00 - 34+61.02	LT	51.0	51.0
34+10.00 - 34+61.02	RT	51.0	51.0
13TH STREET			
44+00.00 - 44+60.98	LT	61.0	61.0
44+00.00 - 44+60.98	RT	61.0	61.0
45+38.98 - 45+51.07	LT	12.1	12.1
45+38.98 - 45+51.07	RT	12.1	12.1
12TH STREET			
54+36.32 - 54+39.32	LT	3.0	3.0
54+36.32 - 54+39.32	RT	3.0	3.0
55+17.28 - 55+60.00	LT	42.6	42.6
55+17.28 - 55+60.00	RT	42.7	42.7
11TH STREET			
64+30.00 - 64+61.00	LT	31.0	31.0
64+30.00 - 64+61.00	RT	31.0	31.0
65+39.00 - 65+51.08	LT	12.1	12.1
65+39.00 - 65+51.08	RT	12.1	12.1
ITEM TOTAL		4568	4568

STORM SEWER															
STATION TO STATION	LOCATION	(52201)	(52202)	(52203)	(52204)	(52207)	(61102)	(61110)	(61113)	(61151)	(61152)	(61156)	(61182)	(65040)	
		RCP CL. III 12-INCH L.F.	RCP CL. III 15-INCH L.F.	RCP CL. III 18-INCH L.F.	RCP CL. III 21-INCH L.F.	RCP CL. III 30-INCH L.F.	CB, TYPE 2 EACH	MH, TYPE 1 EACH	MH, TYPE 5 EACH	MH COVERS, TYPE J EACH	MH COVERS, TYPE K EACH	INLET COVER, TYPE H-S EACH	ADJUSTING MH COVER EACH	CONSTRUCTION STAKING, STORM SEWER SYSTEM EACH	
GRAND AVE.															
101+10.34 - 122+11.00	MAINLINE	519	266	385	416	1119	24	5	1	5	1	24	1	1	
ITEM TOTAL		519	266	385	416	1119	24	5	1	5	1	24	1	1	

PIPE UNDERDRAIN		
STATION TO STATION	LOCATION	(61201)
		PIPE UNDERDRAIN 6-INCH L.F.
GRAND AVE.		
101+10.34 - 105+30.18	LT	400
101+10.34 - 105+30.18	RT	430
105+30.18 - 109+50.23	LT	383
105+30.18 - 109+50.23	RT	403
109+50.23 - 113+70.18	LT	381
109+50.23 - 113+70.18	RT	383
113+70.18 - 117+90.66	LT	382
113+70.18 - 117+90.66	RT	383
117+90.66 - 122+11.00	LT	393
117+90.66 - 122+11.00	RT	393
ITEM TOTAL		3931

DUST CONTROL SURFACE TREATMENT		
STATION TO STATION	LOCATION	(62302)
		DUST CONTROL SURFACE TREATMENT S.Y.
GRAND AVE.		
101+10.34 - 122+11.00	MAINLINE	38718
ITEM TOTAL		38718

TURF ESTABLISHMENT			
STATION TO STATION	LOCATION	(62501)	(63110)
		SALVAGED TOPSOIL S.Y.	LAWN SOD S.Y.
GRAND AVE.			
101+10.34 - 105+30.18	LT	570	570
101+10.34 - 105+30.18	RT	434	434
105+30.18 - 109+50.23	LT	525	525
105+30.18 - 109+50.23	RT	581	581
109+50.23 - 113+70.18	LT	618	618
109+50.23 - 113+70.18	RT	630	630
113+70.18 - 117+90.66	LT	515	515
113+70.18 - 117+90.66	RT	622	622
117+90.66 - 122+11.00	LT	593	593
117+90.66 - 122+11.00	RT	574	574
ITEM TOTAL		5662	5662