

WATER			
STATION TO STATION	LOCATION	(62401)	(63103)
		WATER MGAL	SODDED AREAS MGAL
GRAND AVE.			
101+10.34 - 105+30.18	UNDISTRIBUTED	20	12
ITEM TOTAL		20	12

SIGNING			
STATION TO STATION	LOCATION	(63822)	(63830)
		MOVING SIGNS TYPE II EACH	REMOVING SMALL SIGN SUPPORTS EACH
GRAND AVE.			
101+10.34 - 122+11.00	MAINLINE	28	5
ITEM TOTAL		28	5

TRAFFIC CONTROL		
STATION TO STATION	LOCATION	(64301)
		TRAFFIC CONTROL EACH
GRAND AVE.		
101+10.34 - 122+11.00	MAINLINE	1
ITEM TOTAL		1

GEOTEXTILE FABRIC			
STATION TO STATION	LOCATION	(64501)	(64503)
		GEOTEXTILE FABRIC TYPE SAS S.Y.	GEOTEXTILE FABRIC TYPE DF S.Y.
GRAND AVE.			
101+10.34 - 105+30.18	LT	1073	280
101+10.34 - 105+30.18	RT	1073	280
105+30.18 - 109+50.23	LT	1074	280
105+30.18 - 109+50.23	RT	1074	280
109+50.23 - 113+70.18	LT	1073	280
109+50.23 - 113+70.18	RT	1073	280
113+70.18 - 117+90.66	LT	1075	280
113+70.18 - 117+90.66	RT	1075	280
117+90.66 - 122+11.00	LT	1074	280
117+90.66 - 122+11.00	RT	1074	280
ITEM TOTAL		10738	2800

PAVEMENT MARKING										
STATION TO STATION	LOCATION	(64602)	(64618)	(64710)	(64718)	(64730)	(64734)	(64758)	(64778)	(64782)
		PAVEMENT MARKING 4-INCH EPOXY L.F.	PAVEMENT MARKING, CHANNELIZING, 8-INCH EPOXY L.F.	PAVEMENT MARKING STOP LINE 18-INCH L.F.	PAVEMENT MARKING CROSS WALK 6-INCH L.F.	PAVEMENT MARKING ARROWS TYPE 1 EPOXY EACH	PAVEMENT MARKING ARROWS TYPE 2 EPOXY EACH	PAVEMENT MARKING WORDS (ONLY) EPOXY EACH	PAVEMENT MARKING CURB EPOXY L.F.	PAVEMENT MARKING CURB RAMP EPOXY L.F.
GRAND AVE.										
101+10.34 - 122+11.00	MAINLINE	6306	600	185	1431	2	12	11	1457	387
ITEM TOTAL		6306	600	185	1431	2	12	11	1457	387

CONSTRUCTION STAKING, SUBGRADE		
STATION TO STATION	LOCATION	(65045)
		CONSTRUCTION STAKING, SUBGRADE L.F.
GRAND AVE.		
101+10.34 - 122+11.00	MAINLINE	2101
ITEM TOTAL		2101

PAVEMENT SAWING		
STATION TO STATION	LOCATION	(66501)
		SAWING EXISTING PAVEMENT L.F.
GRAND AVE.		
101+10.34	BEGINNING OF PROJECT	61
105+30.18	LT	40
105+30.18	RT	31
109+50.23	LT	25
109+50.23	RT	24
113+70.18	LT	35
113+70.18	RT	31
117+90.66	LT	25
117+90.66	RT	24
122+11.00	END OF PROJECT	105
ITEM TOTAL		401

SELECTED BORROW EXCAVATION, SPECIAL		
STATION TO STATION	LOCATION	(90035)
		SELECTED BORROW SPECIAL TON
GRAND AVE.		
101+10.34 - 105+30.18	LT	54
101+10.34 - 105+30.18	RT	60
105+30.18 - 109+50.23	LT	70
105+30.18 - 109+50.23	RT	60
109+50.23 - 113+70.18	LT	70
109+50.23 - 113+70.18	RT	70
113+70.18 - 117+90.66	LT	68
113+70.18 - 117+90.66	RT	74
117+90.66 - 122+11.00	LT	68
117+90.66 - 122+11.00	RT	64
ITEM TOTAL		658

POLYSTYRENE INSULATION BOARD		
STATION TO STATION	LOCATION	(90905)
		POLYSTYRENE INSULATION BOARD, 2-INCH S.F.
GRAND AVE.		
103+16.11	20' LT	81
104+95.91	20' LT	81
105+40.17	17' RT	81
105+40.22	47' LT	81
109+16.15	20' LT	81
109+60.21	32' LT	81
109+60.24	17' RT	81
109+60.26	47' RT	81
113+80.17	17' RT	81
113+80.17	33' RT	81
113+85.17	17' RT	81
113+85.17	30' RT	81
117+54.82	20' LT	81
117+80.67	46' LT	81
118+00.65	47' RT	81
118+00.66	17' RT	81
118+00.67	32' LT	81
120+74.00	20' LT	81
ITEM TOTAL		1458

LEVELS ON = 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59