PLAN NOTES ◇

1. CONNECT TO EXISTING SANITARY
2. SEAL 6" COMBINED SEWER PIPE
3. EXTEND SIDEWALK

EXISTING RIGHT OF WAY

MH1

MH2
701+00

NOTE: FIELD VERIFY ALL SERVICE LOCATIONS

CONSTRUCTION LIMITS

GRADE BREAK STA = 700+10.00
ELEV = 650.736

GRADE BREAK STA = 700+55.23
ELEV = 650.415

GRADE BREAK STA = 700+68.45
ELEV = 650.811

GRADE BREAK STA = 700+81.45
ELEV = 650.420

GRADE BREAK STA = 701+59.93
ELEV = 650.729

EXISTING CL

PROPOSED CL

-0.7%

3.0%

-3.0%

0.4%

MH1
RIM:~~650.53~~ 650.86
INV OUT (W):641.31

MH2
RIM:~~650.49~~ 650.71
INV OUT (E):~~640.34~~ 650.56

EX.6" PVC

GAS MAIN (DEPTH ASSUMED)

COLLAR PER CITY STD

EX.10" VCP

GAS MAIN (DEPTH ASSUMED)

COLLAR PER CITY STD

EX.10" VCP

655
650
645
640

1"=10' HORZ.
1"=8' VERT.

SCALE 2.5 FEET

SUPERIOR WISCONSIN	CITY OF SUPERIOR, WI - ENVIRONMENTAL SERVICES DIVISION OF PUBLIC WORKS	NORTH 21ST & BANKS STORM SEWER PROJECT	BANKS SANITARY SEWER PLAN & PROFILE	12/12/18	DRAWN BG / APPROVED EA	SHEET 9 OF 25