



DETAIL SUMMARY OF MISCELLANEOUS QUANTITIES

| MANHOLE & COVER | | | |
|----------------------------------|-----|----------|-------|
| STA | | | |
| 0+25 | 1 | | |
| 3+45 | 1 | | |
| 8" PVC SANITARY SEWER PIPE | | | |
| STA | | LIN. FT. | |
| 0+27 - 3+43 | | 316' | |
| SILT FENCE | | | |
| STA TO STA. | | LIN. FT. | |
| UNDISTRIBUTED | | 100 | |
| SEED AND MULCH AND EROSION BALES | | | |
| | LBS | SO. YDS. | BALES |
| 0+20 TO 3+50 | 30 | 3333 | 6 |

NOTE: EROSION CONTROL TO BE INSTALLED CONSISTENT WITH "WISCONSIN CONSTRUCTION SITE BEST MANAGEMENT PRACTICE" HANDBOOK. ALL EROSION CONTROL TO BE INSTALLED PRIOR TO BEGINNING ANY CONSTRUCTION.

LEVELS ON - 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63

