

EQUIPMENT NOTES

1. CONTRACTOR TO COORDINATE ELECTRICAL REQUIREMENTS
2. CONFIRM HEIGHT AND LOCATION WITH OWNER
3. CONTRACTOR TO PROVIDE SUB-FLOOR AND CARPETING
4. SOLID WOOD BACKING REQ. VERIFY LOCATION IN WALL WITH OWNER PRIOR TO CLOSING WALL
5. FINAL CONNECTION BY CONTRACTOR
6. FINAL CONNECTION BY PLUMBING CONTRACTOR
7. FINAL CONNECTION BY ELECTRICAL CONTRACTOR
8. BO'SUN SUPPLIES, CO MODEL S3705-0010 SIZE 4 304, STAINLESS STEEL STAMPED AND WELDED PAD EYE, MOUNTED VERTICALLY OR EQUAL
9. GC TO COORDINATE ROUTING OF CONDUIT TO TV AND TO MILLWORK WHERE DVD IS LOCATED
10. GC TO PROVIDE SUPPORT NEEDED AND TO COORDINATE WITH AV VENDOR
11. COUNTER TO SUPPORT 840 LBS, MILLWORK SUB TO COORDINATE REQUIREMENTS
12. CURB BY GC. GC TO USE MARINE GRADE PLYWOOD FOR CURB
13. GC TO PROVIDE STAINLESS STEEL COVER FOR FOOT PEDAL
14. GC TO PROVIDE AT ALL JANITOR'S & STORAGE CLOSETS TYPICAL
15. GC TO COORDINATE ROUTING OF CONDUITS FROM MASTER STATION TO MONITORS WITH VENDOR
16. GC TO PROVIDE STRUCTURAL SUPPORT PER STANDARD DETAIL
17. GC TO PROVIDE 48"X3/4"X48" PLYWOOD BACKING, MOUNT AS HIGH ON WALL AS POSSIBLE
18. GC TO COORDINATE WITH OWNER'S VENDOR ON DELIVERY AND PROVISION OF EQUIPMENT
19. OWNER TO COORDINATE ADAPTOR NEEDED FOR SCAVENGE SYSTEM WITH MEDICAL GAS COMPANY
20. GC TO FINISH EXPOSED PIPING WITH BLANK PLAM CABINET BOX

GENERAL NOTES

1. THE GENERAL CONTRACTOR IS TO COORDINATE W/ OWNER, PRIOR TO CONSTRUCTION, THE DELIVERY, HANDLING, SEQUENCE, EQUIPMENT SIZES, & UTILITY CONNECTIONS REQUIRED FOR ANY EQUIPMENT SCHEDULED TO BE PROVIDED BY OWNER & INSTALLED BY CONTRACTOR. COORDINATE SCHEDULING TO PROVIDE FOR TIMELY ORDERING OF EQUIPMENT, SHOP DRAWINGS IF REQUIRED, INSTALLATION, ETC. TO AVOID DELAY OF CONSTRUCTION.
2. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL LOCATIONS OF COMPUTER/DATA OUTLETS
3. RE: MEP DRAWINGS & SPECIFICATIONS FOR ADDITIONAL INFORMATION
4. MEDICAL GAS AND SUCTION FROM CEILING U.N.O.
5. ALL OUTLETS WITHIN TUB TABLES IN DENTAL TO BE INSTALLED BY MANUF. OF TUB TABLES
6. OWNER TO COORDINATE LOCATION & REQUIREMENTS FOR EYEWASH STATIONS
7. S.S. CORNER GUARDS AND END GUARDS TO BE PROVIDED ON ALL GYP. WALL OUTSIDE CORNERS EXCEPT @ TILE WAINSCOTING
S.S END GUARDS TO BE PROVIDED FULL HEIGHT AT END WALLS AROUND CAGE BANKS IN WET AREAS.
8. RE: EQUIPMENT PLAN FOR EQUIPMENT LOCATIONS

EQUIPMENT SCHEDULE

EQUIPMENT SYMBOL

FINISHED BY CONTRACTOR
 PLUMBING BY OWNER
 INSTALLED BY CONTRACTOR
 BLOCKING REQUIRED
 ELECTRICAL REQUIRED
 WATER/SEWER REQUIRED

NO.	EQUIPMENT DESCRIPTION								
GENERAL OFFICE EQUIPMENT									
1-1.04	STAINLESS STEEL SHELVES		X	X					WALL MOUNTED
FURNITURE & SIGNAGE									
2-1.01	CHAIRS		X	X					
2-1.02	TABLE		X	X					
COMMUNICATION & SECURITY									
3-1.01	COMPUTER		X	X	X	X			
3-2.01	TELEPHONE - COUNTER		X	X	X	X			
3-3.01	CREDIT CARD MACHINE		X	X	X	X			
3-4.01	TELEVISION - WALL MOUNTED		X	X	X	X		2	
3-5.03	COPIER/PRINTER ON STAND		X	X	X	X			
3-5.04	COPIER/PRINTER ON COUNTER		X	X	X	X			
3-6.05	ELECTRICAL PANEL	X	X	X	X	X			
3-8.09	WEBCAM - WALL MOUNTED		X	X	X	X		1B	
3-9.02	PROJECTION SCREEN		X	X	X	X		1, 10	
3-9.03	PROJECTOR		X	X	X	X		1, 10	
APPLIANCES									
4-1.02	REFRIGERATOR - FULL SIZE W/ WATER LINE	X	X	X	X	X			
4-1.03	REFRIGERATOR - UNDER COUNTER		X	X	X	X			
4-1.07	FREEZER - RESIDENTIAL CHEST		X	X	X	X			
4-2.04	WASHER - COMMERCIAL		X	X	X	X			
4-2.05	DRYER - COMMERCIAL		X	X	X	X			
4-4.01	DISHWASHER - ADA ACCESSIBLE HT 34"		X	X	X	X			
4-4.03	DISHWASHER - FREESTANDING COMM		X	X	X	X			
4-6.02	ELECTRIC WATER COOLER	X	X	X	X	X			
4-6.03	GARBAGE DISPOSAL	X	X	X	X	X			
MEDICAL EQUIPMENT									
5-1.01	ANESTHESIA/PATIENT MONITORING		X	X	X	X			
5-3.03	EXAM LIGHT - SINGLE CEILING MOUNTED		X	X	X	X		16, 18	
5-4.01	CENTRIFUGE		X	X	X	X			
5-4.06	MICROSCOPE - SINGLE		X	X	X	X			
5-5.04	ANESTHESIA SCAVENGER OUTLET		X	X	X	X		2	
5-5.08	ANESTHESIA SCAVENGER FAN		X	X	X	X		FOR WASTE ANESTH ONLY	
5-7.01	STAINLESS STEEL GROOMING TUB		X	X	X	X		6, 18	
5-7.03	STAINLESS STEEL TUB TABLE		X	X	X	X		6, 18	
CAGING/RUNS									
7-1.01	CAGES ON CURBS		X	X				12	
7-1.02	CAGES ON WHEELS		X	X					
7-2.02	RUN GATE		X	X					
7-2.03	RUN SIDE PANEL		X	X					
7-2.04	RUN BACK PANEL		X	X					
7-2.06	GUILLOTINE DOOR		X	X					
PLUMBING - GENERAL									
9-1.01	S.S. KITCHEN SINK - SINGLE	X	X						X
9-1.03	BAR SINK (EXAM SINK)	X	X						X
9-1.04	MOP SINK	X	X		X				RE: STANDARD DTL.
9-1.08	UTILITY SINK	X	X		X				X
9-1.09	FLUSH DRAIN - IN CATCH BASIN	X	X		X				X
9-1.13	WALL MOUNTED LAVATORY	X	X		X				X
9-2.01	HOSE BIB	X	X		X				X
9-2.02	HOSE REEL	X	X		X				X
9-3.01	FLOOR DRAIN	X	X						X
9-3.02	TRENCH DRAIN	X	X						X
9-3.03	FLOOR SINK	X	X						X
9-4.09	SPRAYER	X	X						X