

EQUIPMENT NOTES

1. CONTRACTOR TO COORDINATE ELECTRICAL REQUIREMENTS
2. CONFIRM HEIGHT AND LOCATION WITH OWNER
3. CONTRACTOR TO PROVIDE SUB-FLOOR AND CARPETING
4. SOLID WOOD BACKING REQ. VERIFY LOCATION IN WALL WITH OWNER PRIOR TO CLOSING WALL
5. FINAL CONNECTION BY CONTRACTOR
6. FINAL CONNECTION BY PLUMBING CONTRACTOR
7. FINAL CONNECTION BY ELECTRICAL CONTRACTOR
8. BO'SUN SUPPLIES.CO MODEL S8705-0010 SIZE 4 304, STAINLESS STEEL STAMPED AND WELDED PAD EYE, MOUNTED VERTICALLY OR EQUAL
9. GC TO COORDINATE ROUTING OF CONDUIT TO TV AND TO MILLWORK WHERE DVD IS LOCATED
10. GC TO PROVIDE SUPPORT NEEDED AND TO COORDINATE WITH AV VENDOR
11. COUNTER TO SUPPORT 840 LBS, MILLWORK SUB TO COORDINATE REQUIREMENTS
12. CURB BY GC. GC TO USE MARINE GRADE PLYWOOD FOR CURB
13. GC TO PROVIDE STAINLESS STEEL COVER FOR FOOT PEDAL
14. GC TO PROVIDE AT ALL JANITOR'S & STORAGE CLOSETS TYPICAL
15. GC TO COORDINATE ROUTING OF CONDUITS FROM MASTER STATION TO MONITORS WITH VENDOR
16. GC TO PROVIDE STRUCTURAL SUPPORT PER STANDARD DETAIL
17. GC TO PROVIDE 48"X3/4"X48" PLYWOOD BACKING, MOUNT AS HIGH ON WALL AS POSSIBLE
18. GC TO COORDINATE WITH OWNER'S VENDOR ON DELIVERY AND PROVISION OF EQUIPMENT
19. OWNER TO COORDINATE ADAPTOR NEEDED FOR SCAVENGE SYSTEM WITH MEDICAL GAS COMPANY
20. GC TO FINISH EXPOSED PIPING WITH BLANK PLAM CABINET BOX

FLOOR PLAN KEY NOTES

SYMBOL	DESCRIPTION
①	PROVIDE POWER AND DATA
②	DETERGENT STORAGE
③	PROVIDE POWER AND DATA FOR 6 WORK STATIONS
④	COMMERCIAL DISHWASHER TO BE INSTALLED AT LATER DATE, PROVIDE POWER AND WATER AS REQ.
⑤	
⑥	

GENERAL NOTES

1. THE GENERAL CONTRACTOR IS TO COORDINATE W/ OWNER, PRIOR TO CONSTRUCTION, THE DELIVERY, HANDLING, SEQUENCE, EQUIPMENT SIZES, & UTILITY CONNECTIONS REQUIRED FOR ANY EQUIPMENT SCHEDULED TO BE PROVIDED BY OWNER & INSTALLED BY CONTRACTOR. COORDINATE SCHEDULING TO PROVIDE FOR TIMELY ORDERING OF EQUIPMENT, SHOP DRAWINGS IF REQUIRED, INSTALLATION, ETC. TO AVOID DELAY OF CONSTRUCTION.
2. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL LOCATIONS OF COMPUTER/DATA OUTLETS
3. RE: MEP DRAWINGS & SPECIFICATIONS FOR ADDITIONAL INFORMATION
4. S.S. CORNER GUARDS AND END GUARDS TO BE PROVIDED ON ALL GYP. WALL OUTSIDE CORNERS EXCEPT @ TILE MAINSCOTING
S.S END GUARDS TO BE PROVIDED FULL HEIGHT AT END WALLS AROUND GAGE BANKS IN WET AREAS.
5. RE: EQUIPMENT PLAN FOR EQUIPMENT LOCATIONS
6. BUILDING TO HAVE WIRELESS ACCESS THROUGHOUT.

EQUIPMENT SCHEDULE

○ EQUIPMENT SYMBOL

FURNISHED BY CONTRACTOR
 FURNISHED BY CITY
 INSTALLED BY PLUMBING SOCIETY
 INSTALLED BY CONTRACTOR
 ELECTRICAL REQUIRED
 WATER/SEWER REQUIRED

NO.	EQUIPMENT DESCRIPTION								
GENERAL OFFICE EQUIPMENT									
1-1.04	STAINLESS STEEL SHELVES		X	X					
FURNITURE & SIGNAGE									
2-1.01	CHAIRS		X	X					
2-1.02	TABLE		X	X					
2-1.11	DESK		X	X					
COMMUNICATION & SECURITY									
3-1.01	COMPUTER		X	X	X				
3-2.01	TELEPHONE - COUNTER		X	X	X				
3-3.01	CREDIT CARD MACHINE		X	X	X				
3-4.01	TELEVISION - WALL MOUNTED		X	X	X			2	
3-5.03	COPIER / PRINTER ON STAND		X	X	X				
3-5.04	COPIER / PRINTER ON COUNTER		X	X	X				
3-6.05	ELECTRICAL PANEL	X		X	X				
3-8.09	WEBCAM - WALL MOUNTED		X	X	X				
3-9.02	PROJECTION SCREEN		X	X	X	X		1, 10	
3-9.03	PROJECTOR		X	X	X	X		1, 10	
3-9.04	SPEAKERS		X	X	X	X		1, 10	
APPLIANCES									
4-1.02	REFRIGERATOR - FULL SIZE W/ H2O LINE		X	X	X	X			
4-1.03	REFRIGERATOR - UNDER COUNTER		X	X	X				
4-1.04	REFRIGERATOR - APARTMENT SIZE		X	X	X				
4-1.07	FREEZER - RESIDENTIAL CHEST		X	X	X				
4-2.04	WASHER - COMMERCIAL		X	X	X	X			
4-2.05	DRYER - COMMERCIAL		X	X	X				
4-4.01	DISHWASHER - ADA ACCESSIBLE HT 34"		X	X	X	X			
4-6.02	ELECTRIC WATER COOLER	X	X	X	X	X			
4-6.03	GARBAGE DISPOSAL	X	X	X	X	X			
MEDICAL EQUIPMENT									
5-1.21	CONTROLLED SUBSTANCE CAB - SURFACE MNTD		X	X	X				
5-2.03	LIFT TABLE		X	X	X			EXISTING, RELOCATE	
5-3.03	EXAM LIGHT - SINGLE CLG MOUNTED	X	X	X	X			16, 18	
5-4.01	CENTRIFUGE		X	X	X				
5-4.06	MICROSCOPE - SINGLE		X	X	X				
5-7.01	STAINLESS STEEL GROOMING TUB	X	X	X	X	X		6, 18	
CAGING/RUNS									
7-1.01	CAGES ON CURBS		X	X				12	
7-1.02	CAGES ON CURBS		X	X					
7-2.02	RUN GATE		X	X					
7-2.03	RUN SIDE PANEL		X	X					
7-2.04	RUN BACK PANEL		X	X					
7-2.06	GUILLOTINE DOOR		X	X					
PLUMBING - GENERAL									
9-1.01	SS KITCHEN SINK - SINGLE		X	X				X	
9-1.02	SS SCULLERY SINK - DOUBLE		X	X				X	
9-1.03	BAR SINK (EXAM SINK)		X	X				X	
9-1.04	MOP SINK		X	X	X	X		RE: STANDARD DETAIL	
9-1.05	UTILITY SINK		X	X				X	
9-1.09	FLOOR DRAIN - IN CATCH BASIN		X	X				X	
9-1.13	WALL MOUNTED LAVATORY		X	X				X	
9-1.14	MOP SINK - W/ SS ENCLOSURE		X	X				X	
9-2.01	HOSE BIB		X	X				X	
9-2.02	HOSE REEL		X	X	X	X		X	
9-3.01	FLOOR DRAIN		X	X				X	
9-3.02	TRENCH DRAIN		X	X				X	
9-3.03	FLOOR SINK		X	X				X	
9-4.03	EYEWASH STATION - COUNTER MOUNTED		X	X				X	
9-4.09	SPRAY WAND		X	X				X	
9-6.03	HAIR TRAP		X	X				X	